

序号	起讫桩号	长度 (m)	处治面积 (m ²)	清除表土面积 (m ²)	挖除砼板块 (m ³)	翻松掺4%石灰 (m ²)	中部填4%石灰土 (m ³)	素土填土 (m ³)	路床6%石灰土 (m ³)	反开挖体积 (m ³)	超宽碾压 (m ³)	路肩培土 (m ³)	备注	
1	K0+006.995 ~ K0+378.192	371.2	5975.6	5523.6	80.0	4117.5		1000.0	3056.4	1548.0	133.6	185.6	清表厚度按20cm计 翻松处理厚度按20cm计 超宽碾压一边按0.3m计	
合计		371.2	5975.6	5523.6	80.0	4117.5		1000.0	3056.4	1548.0	133.6	185.6		

序号	起 迄 桩 号		工程位置	工程数量(立方米)			水塘回填数量 (m ³)			钢塑格栅	备 注	
				清淤	排水	挖台阶	碎石土	4%石灰土	素土	(m ²)		
	I. 清淤											
1	K0+135.0	~	K0+172.0	中间	233.6	292.0	124.7		676.2	239.8	368.0	全填
	合计				233.6	292.0	124.7		676.2	239.8	368.0	

